Palm & Tree Removal Proposal: Verona Walk

Submitted to Verona Walk by Greenscapes | Proposal #1483692 | October 30, 2026

Proposal details	
Submitted to	Verona Walk
Submitted by	Greenscapes, Linzy Clark
Project	Verona Walk Removals October
Service location	7375 Veronawalk Cir, Naples, Florida 34114
Survey dates	October 16 and October 30, 2026
Scope of work	Removal and Grind, 64 trees
Proposal value	**$12,450**

Summary

Greenscapes recommends removing **64 declining or dead trees** throughout Verona Walk, each with stump grinding, for a total of **$12,450**. Queen Palms make up 51 of the 64 trees (about 80%). The rest are a small number of other palms and one Southern Live Oak.

Our team surveyed the community on October 16 and October 30, 2026. For every tree we recorded a photo, species, mapped location, recommended service, and suspected cause of decline. The full photo record and a color-coded map are included with the proposal.

Trees and Pricing

Species	Count	Price each	Subtotal
Queen Palm	51	$150	$7,650
Foxtail Palm	5	$150	$750
Coconut Palm	3	$900 / $500 / $500	$1,900
Southern Live Oak	1	$750	$750
Bismarck Palm	1	$600	$600
Medjool Date Palm	1	$500	$500
Pygmy Date Palm	1	$150	$150
Cabbage Palm	1	$150	$150
Total	**64**		**$12,450**

Queen, Foxtail, Pygmy Date, and Cabbage Palms are priced at $150 each. Six trees are priced individually: the three Coconut Palms, the Southern Live Oak, the Bismarck Palm, and the Medjool Date Palm. Together they total $3,750, or about 30% of the proposal.

Why We Recommend Removal

We noted a suspected cause for most trees. Some trees show more than one issue, so these counts are approximate and come directly from our field notes.

Suspected cause	Approx. trees	What it means
Wilt	24	Progressive collapse of fronds and crown decline. Mostly Queen Palms.
Boron deficiency	15	A micronutrient problem that distorts new growth. Common in Queen Palms in Florida.
Ganoderma	8	A fungal butt rot at the base of the trunk. It is not curable, and affected palms eventually fall.
General decline	5	Gradual loss of health without a single clear cause.
Lightning	3 Coconut Palms, 2 possible Queen Palms	Strike damage to the crown and trunk.
Palm borer	1	Bismarck Palm.
Other notes	5	No new growth, damaged new growth, advanced decline, or cause uncertain.
No cause noted	5	Includes the Live Oak, two Foxtail Palms, and two Queen Palms.

Safety: Palms with Ganoderma can fail at the base with little warning, and palms in advanced wilt or decline are likely to drop heavy fronds or fall. Many of these trees stand close to homes, vehicles, sidewalks, and screen enclosures. Prompt removal reduces risk to residents and property.

Where the Trees Are

Street	Trees
Alessandria Ct	6
Marconi Ct	6
Garibaldi Ct / Court	4
Orvieto Ct	4
Sicilia Ct	4
Valentina Ct	4
Wilfredo Ct	4
Benelli Ct	3
Julia Ln	3
Portofino Ct	3
Salerno Ct	3
Xenia Ln	3
Genova Ct	2
Karina Ct	2
Leopardi Ct	2
Tommasi Ct	2
Single-tree streets (Bellini Way, Deimille Ct, Novara Ct, Ravello Ct, Rimini Way, Toscana Ct, Verducci Ct, Veronawalk Cir, Zurigo Ln)	9

The proposal's map shows every tree by location, and the itemized list gives each tree's street address. Three addresses (7589 Garibaldi Ct, 7824 Orvieto Ct, and 8511 Alessandria Ct) each have two trees.

Individually Priced Trees

Tree	Address	Price	Noted cause
Coconut Palm	8498 Deimille Ct	$900	Lightning
Southern Live Oak	8801 Zurigo Ln	$750	None noted
Bismarck Palm	7616 Garibaldi Ct	$600	Palm borer
Coconut Palm	8887 Ravello Ct	$500	Lightning
Coconut Palm	8902 Verducci Ct	$500	Lightning
Medjool Date Palm	7375 Veronawalk Cir	$500	Ganoderma

Scope of Work

Every tree in this proposal receives the **Removal and Grind** service:

- Complete removal of the tree.
- Stump grinding to the depth the grinder wheel can reach, typically 8–12 inches below grade.
- Surface roots are not ground unless specified.
- Wood, brush, and debris incidental to the work are removed by Greenscapes.
- Replacement planting is not part of this proposal.

Greenscapes carries liability insurance for injury to persons or property, and all employees are covered by Workers Compensation Insurance.

Terms

- **Scheduling:** Crews arrive at the job site unannounced unless otherwise noted. We will attempt to meet all performance dates but are not liable for delays caused by weather or other circumstances beyond our control.
- **Utilities:** The customer must identify all non-public utilities, such as irrigation lines, landscape lighting, and private cables. Greenscapes assumes no responsibility for underground utilities that are not clearly marked before work begins. Stump grinding and removals will occur where public utilities allow.
- **Ownership and permission:** The customer warrants that all trees and property involved are owned by the customer or that the owner has given permission for the work, and holds Greenscapes harmless from claims arising from a failure to obtain that permission.
- **Payment:** Accounts are net payable upon receipt of invoice. A 1.5% service charge is added to balances not fully paid 30 days after the invoice date. If outside assistance is used to collect, the customer is responsible for collection costs, including attorney fees and court costs.

Approval and Next Steps

1. Review this proposal and the attached tree map and photo record.
2. Sign and return the proposal to authorize the work.
3. Ensure residents mark private irrigation, lighting, and other buried lines before crews arrive, and confirm homeowner permission for trees on private lots.
4. Greenscapes will schedule the removals. We are glad to discuss timing and sequencing by street.

We appreciate the opportunity to serve Verona Walk and are available to walk the site or answer questions at any time.

Contact

Linzy Clark, Greenscapes
lclark@greenscapesfl.com | 239-877-2552
Proposal #1483692, dated October 30, 2026